

Project Fairway

Space Requirements & Facility Specifications

Prepared for: Workhouse Arts Center Inquiry

Prepared by: Russell Evans

Date: July 2026

Version: 1.0

Phase 1: Two premium simulator bays with expansion path to four bays.

Executive Summary

Project Fairway requires a dedicated commercial space to house a premium indoor golf experience. The initial build (Phase 1) includes two full-size simulator bays, a small reception/lounge area, a mechanical/storage room, and a restroom. Phase 2 expands to four bays by utilizing adjacent or contiguous space planned from day one.

Metric	Phase 1 (2 Bays)	Phase 2 (4 Bays)
Simulator Bays	2	4
Bay Area (each)	~225-270 sq ft	~225-270 sq ft
Total Bay Footprint	~500-540 sq ft	~1,000-1,080 sq ft
Common / Lounge Area	~200-300 sq ft	~350-500 sq ft
Support Spaces	~150-200 sq ft	~200-300 sq ft
Total Square Footage	~1,200-1,600 sq ft	~2,200-3,000 sq ft
Min. Ceiling Height	10 ft (12 ft ideal)	10 ft (12 ft ideal)
Electrical Service	200A minimum	400A recommended

Individual Bay Specifications

Each simulator bay must accommodate a full golf swing, ball flight projection, and comfortable seating for spectators. These dimensions are based on premium commercial simulator installations (TrackMan, Foresight GCQuad, Uneekor QED-class systems).

Minimum Bay Dimensions

Dimension	Minimum	Recommended	Notes
Width	12 ft	15 ft	Allows full swing clearance + seating
Depth	16 ft	18-20 ft	Screen to back wall; includes hitting area + seating
Ceiling Height	10 ft	12 ft	Critical for tall golfers with driver
Screen Width	10 ft	12-14 ft	Impact screen dimension
Screen Height	8 ft	9-10 ft	Floor to top of impact screen
Hitting Distance	8 ft	10-12 ft	From impact screen to hitting mat

Note: At 15 ft wide x 18 ft deep, each bay is approximately 270 sq ft. A more compact 12 ft x 18 ft configuration yields ~216 sq ft per bay but limits the premium lounge feel.

Bay Layout (Front to Back)

- Impact screen + enclosure frame (1-2 ft depth from wall)
- Ball flight zone (6-8 ft clear space)
- Hitting position / mat + auto-tee system (4 ft)
- Launch monitor position (overhead or rear-mount, 2-4 ft)
- Seating / lounge area (4-6 ft behind hitting area)
- Bay dividers (ceiling-mounted retractable nets or solid partitions)

Total Facility Layout

Phase 1 - Two Bay Configuration (~1,200-1,600 sq ft)

The Phase 1 layout prioritizes a premium two-bay experience with enough common space to feel like a club, not a closet. The layout should be designed so that the expansion wall (separating Phase 1 from the future Phase 2 space) can be opened up without major structural work.

Zone	Dimensions	Square Footage	Purpose
Bay 1	15 ft x 18 ft	270 sq ft	Simulator + seating
Bay 2	15 ft x 18 ft	270 sq ft	Simulator + seating
Lounge / Reception	~15 ft x 16 ft	~240 sq ft	Check-in kiosk, seating, welcome screen
Hallway / Circulation	varies	~120 sq ft	Access between zones
Mechanical / Storage	~8 ft x 10 ft	~80 sq ft	HVAC, networking, cleaning supplies
Restroom	~6 ft x 8 ft	~48 sq ft	ADA-compliant single restroom
TOTAL		~1,028-1,600 sq ft	Range accounts for wall thickness and layout efficiency

Phase 2 - Four Bay Expansion (~2,200-3,000 sq ft total)

Phase 2 adds two additional bays and expands the lounge area. Ideally the space is leased from day one with the expansion area used as flexible/event space until demand justifies the build-out, or an adjacent unit is secured with a right of first refusal.

Addition	Square Footage	Notes
Bay 3	270 sq ft	Mirror of Bay 1/2 configuration
Bay 4	270 sq ft	Mirror of Bay 1/2 configuration
Expanded Lounge	+150-250 sq ft	More seating, potential bar/beverage area
Additional Storage	+50-100 sq ft	Club storage, merchandise
Second Restroom	+48 sq ft	Required with increased occupancy
Phase 2 Addition	~800-940 sq ft	Added to Phase 1 footprint

Infrastructure & Utility Requirements

Ceiling Height (Critical)

This is the single most important structural requirement and the hardest to modify after the fact.

- **Absolute minimum:** 10 feet clear (floor to lowest obstruction — not joists, not HVAC, not sprinklers)
- **Recommended:** 11-12 feet clear
- **Why:** A 6'2" golfer with a driver at full backswing extension reaches approximately 9'3". Add the club head arc and you need clearance above that. 10 ft is tight. 12 ft is comfortable.
- **Measure to:** Bottom of joists, bottom of HVAC ductwork, sprinkler heads — whichever is lowest

Electrical

Golf simulators are power-hungry. Each bay runs a high-lumen projector, a gaming PC, a launch monitor, lighting, speakers, and potentially an auto-tee system and ball return.

Component	Power Draw (per bay)	Circuit Requirement
Projector (4K short-throw)	400-800W	Dedicated 20A circuit
Gaming PC	500-800W	Dedicated 20A circuit
Launch Monitor	50-150W	Shared circuit OK
Auto-tee + Ball Return	200-500W	Dedicated 20A circuit
Lighting + AV	200-400W	Shared circuit
HVAC (supplemental)	1,500-3,000W	Dedicated 30A or 40A
Per Bay Total	~2,500-5,000W	3-4 dedicated circuits per bay

Total facility requirement (Phase 1): 200A service minimum. Plan for 400A if expansion is likely — upgrading electrical service later is expensive and disruptive.

HVAC / Climate Control

Projectors and PCs generate significant heat. Each bay produces approximately 5,000-10,000 BTU/hr of waste heat. A two-bay facility needs supplemental cooling beyond what a typical commercial lease provides.

- **Estimate:** 1-2 additional tons of cooling per bay (on top of base HVAC)
- **Options:** Mini-split systems (most flexible), supplemental roof-mounted units, or upgraded existing system
- **Ventilation:** Fresh air circulation to prevent stuffiness during back-to-back sessions
- **Temperature target:** 68-72°F consistent — golfers are active and generate body heat
- **Ask:** What is the existing HVAC capacity (tonnage) and can supplemental units be added?

Networking & Connectivity

- **Internet:** Business-class fiber preferred (minimum 100 Mbps symmetric). Simulators stream course data and software updates.
- **Internal network:** Hardwired CAT6 to each bay (do not rely on WiFi for simulator PCs)
- **WiFi:** Separate network for customer devices and Bluetooth speakers
- **Low-voltage runs:** Plan conduit during build-out for network, AV, and access control cabling

Acoustics & Soundproofing

Golf ball impacts on screen produce 85-95 dB peaks. Without treatment, this carries through walls and between bays. This is especially relevant at the Workhouse given adjacent art studios and galleries.

- Acoustic panels on shared walls and ceiling
- Bay dividers with sound-dampening material (not just curtains)
- Impact screens themselves absorb significant sound
- Rubber flooring / thick turf on concrete absorbs floor vibration
- **Ask:** Are there noise restrictions or quiet-hour requirements on campus?

Structural & Access Requirements

Floor

- **Level concrete slab preferred** — no significant slope across the hitting area
- Floor must support simulator enclosure framing (anchored to slab)
- Finished floor: turf/mat in hitting zone, luxury vinyl plank or polished concrete in lounge

Doors & Loading

- **Customer entrance:** Standard commercial door (ADA compliant, 36" minimum)
- **Equipment loading:** Need at least one opening 8 ft wide x 8 ft tall for screen frames, projector mounts, and furniture delivery. Roll-up door or double door.
- **Access control:** Door frame must support electronic lock (for member self-service entry)

Plumbing

- Restroom requires water supply and drain (verify existing stub-outs)
- Small sink/wet bar area desirable for lounge (coffee, water)
- **Ask:** Is plumbing already stubbed in or does it need to be run?

Parking

- Minimum 6-8 dedicated spots for Phase 1 (groups of 4 per bay + overlap)
- 12-16 spots for Phase 2
- **Ask:** Are parking spots included in the lease or shared campus parking?

Expansion Strategy

The goal is to minimize cost and disruption when expanding from 2 to 4 bays. There are three approaches, ranked by preference:

Option A: Lease the full footprint on Day 1 (Preferred)

- Lease ~2,200-3,000 sq ft from the start
- Build out Phase 1 (2 bays + lounge) on one side
- Use remaining space as flexible event area / mini putting / lounge overflow
- When demand justifies, build out Bays 3-4 without relocating or negotiating new lease
- **Pros:** Simplest expansion, no business disruption, event space generates interim revenue
- **Cons:** Higher rent from Day 1 before full utilization

Option B: Adjacent Unit with Right of First Refusal

- Lease ~1,200-1,600 sq ft for Phase 1
- Negotiate ROFR (right of first refusal) on adjacent unit
- Design shared wall for easy knock-through (no load-bearing, no major utilities in that wall)
- **Pros:** Lower initial rent
- **Cons:** Risk that adjacent space is unavailable when needed; expansion construction disrupts operations

Option C: Relocate at Expansion

- Least preferred — moving is expensive and disrupts membership continuity
- Only consider if no other options exist at Workhouse

Questions for Your Workhouse Contact

Use this checklist during your conversation. These questions will help you quickly determine whether a given space can work and what modifications would be needed.

Space & Structure

- What spaces are currently available in the 1,200-3,000 sq ft range?
- What is the clear ceiling height (floor to lowest obstruction)?
- Is there a concrete slab floor? Is it level?
- Are there load-bearing interior walls that limit open floor plan?
- Is there a loading door or large access point for equipment delivery?
- Can we see floor plans for available units?

Utilities & Infrastructure

- What is the electrical service capacity (amperage) to the unit?
- Can the panel be upgraded to 200A or 400A if needed?
- What HVAC is included? What tonnage?
- Can supplemental HVAC (mini-splits) be installed?
- Is fiber internet available on campus?
- Is plumbing stubbed in for restroom?

Lease & Terms

- What are the lease terms (NNN, modified gross, full service)?
- What is the rate per square foot?
- Is there a tenant improvement (TI) allowance?
- What lease length is required?
- Is expansion into adjacent space possible (ROFR)?
- Are build-out modifications permitted (framing, electrical, HVAC)?

Campus & Operations

- What are the campus hours of operation? Can we operate evenings/weekends?
- Are there noise restrictions?
- Is signage allowed? What are the guidelines?
- Is alcohol service permitted (beer/wine from brewery partnership)?
- How does parking work? Dedicated or shared?
- What insurance requirements exist for tenants?
- Are there other food/beverage tenants we could partner with?

Alignment & Vision

- How does the Workhouse evaluate new tenant concepts? What makes a good fit?
- Are there community programming opportunities (youth clinics, charity events)?
- Would cross-promotion with campus events be supported?

Deal-Breakers & Non-Negotiables

If any of the following cannot be resolved, the space will not work regardless of other factors:

Requirement	Minimum Threshold	Why It's Critical
Ceiling Height	10 ft clear	Cannot swing a driver safely below this
Electrical Capacity	200A (upgradeable)	Simulators will trip breakers without sufficient power
Bay Width	12 ft per bay	Safety clearance for full swing
Bay Depth	16 ft per bay	Screen + hitting zone + monitor placement
Evening/Weekend Hours	Open until 10 PM	Peak demand is after work and weekends
Build-Out Permission	Framing, electrical, HVAC	Simulator enclosures require structural mounting

Conceptual Layout (Phase 1)

This is a simplified spatial diagram. A proper architectural drawing should be commissioned once a specific unit is identified.

IMPACT SCREEN	IMPACT SCREEN	
BAY 1 15 ft x 18 ft Hitting Zone Launch Monitor Lounge Seating	BAY 2 15 ft x 18 ft Hitting Zone Launch Monitor Lounge Seating	LOUNGE ~15 ft x 16 ft Welcome Screen Kiosk Seating Beverage Area
		MECH / WC Storage + Restroom
	← EXPANSION WALL → Future Bays 3 & 4	ENTRY

Approximate total footprint: 45-48 ft wide x 30-35 ft deep = ~1,350-1,680 sq ft

Recommended Next Steps

After your conversation with the Workhouse contact:

- **Get dimensions:** Request floor plans or schedule a walk-through with a tape measure
- **Measure ceiling:** Bring a laser measure — check multiple points (HVAC drops, beams, sprinklers)
- **Photo-document:** Photograph electrical panel, HVAC units, existing plumbing, floor condition
- **Get lease terms in writing:** Rate/sq ft, TI allowance, lease length, permitted modifications
- **Ask about other tenants:** Who's next door? Noise-sensitive? Complementary?
- **Report back:** With these details, we can build a financial model and determine if the unit works